

[Your Construction Firm Name]

Civil Contractors & Turnkey Builders

Address line 1, City · GST: _____

Phone: _____ · Email: _____

QUOTATION

Quote No. **Q-2026-MUR-01**

Date **03 Aug 2026**

Valid till **02 Sep 2026**

Currency **INR (₹)**

CLIENT & PROJECT DETAILS

Client	Mr. Murali	Project	Residential Building
Plot size	30' × 60' (1,800 sq ft)	Scope	Ground floor (as per plan)
Configuration	2 self-contained portions	Est. built-up area	1,100 sq ft
Type of work	Turnkey (labour + material)	Quality package	Standard finish

Accommodation (per plan): Portion A — Master Bedroom, Bedroom 2, Living, Kitchen, 2 Bath/Toilets · Portion B — Bedroom, Living, Kitchen, 2 Bath/Toilets · Common staircase (provision for upper floor).

A. TURNKEY COST SUMMARY

BUILT-UP AREA

1,100 sq ft

Ground floor, incl. walls

RATE (TURNKEY)

₹ 2,000/sq ft

Standard package

BASIC ESTIMATE

₹ 22,00,000

Before taxes & extras

ESTIMATED TURNKEY COST (GROUND FLOOR)

₹ 22,00,000

Add an upper floor? An identical first floor (G+1) is charged at ~₹ 1,850/sq ft (no fresh foundation/plinth), i.e. approx. **₹ 20,35,000** extra. Stair, sump & overhead tank already provided in the ground-floor scope.

B. DETAILED COST BREAK-UP (BOQ)

#	WORK ITEM	SCOPE / SPECIFICATION	AMOUNT (₹)
1	Site prep & earthwork	Excavation, PCC, anti-termite, backfilling	1,10,000
2	Foundation & RCC	Footings, columns, plinth, beams & roof slab — M20/Fe500	4,40,000
3	Brick / block masonry	9" external & 4½" internal walls	2,20,000
4	Plastering	Internal & external cement plaster	1,75,000
5	Flooring & tiling	Vitrified floor tiles + toilet/kitchen dado & skirting	2,65,000
6	Doors & windows	Main teak door, other flush doors, UPVC/steel windows & grills	2,20,000
7	Electrical	Concealed wiring, points, MCB DB, modular switches (std)	1,75,000
8	Plumbing & sanitary	CPVC/UPVC lines, CP fittings, WCs, wash basins (std brand)	1,75,000
9	Painting	Interior emulsion + exterior weather-coat, 2 coats + primer/putty	1,55,000
10	Waterproofing	Toilets, sunken slabs & roof	45,000
11	Staircase & railing	RCC stair + MS/SS railing	65,000
12	Sump, OH tank & misc.	Underground sump, overhead tank, site clean-up	55,000
Total (Ground Floor, turnkey — Standard package)			₹ 22,00,000

The break-up above is indicative and totals to the turnkey estimate in Section A. Individual line items may vary within the total based on final material selections.

INCLUSIONS & EXCLUSIONS

Included

- All structural & finishing labour and materials as above
- Standard-brand cement, TMT steel, tiles, sanitary & electrical fittings
- Water & electricity charges during construction
- Structural design & construction supervision

Not included (extra, if required)

- Government approvals, plan sanction & deposits
- Compound wall, gate, external paving & landscaping
- Modular kitchen, wardrobes, false ceiling, designer lighting
- EB service connection, borewell & GST (extra as applicable)
- Soil filling / rock excavation beyond normal soil

PAYMENT SCHEDULE

#	STAGE	%	AMOUNT (₹)
1	Advance / booking (before start)	10%	2,20,000
2	On foundation & plinth completion	20%	4,40,000
3	On roof slab casting	25%	5,50,000
4	On brickwork & plastering	20%	4,40,000
5	On flooring, doors & fittings	15%	3,30,000
6	On handover (painting & finishing)	10%	2,20,000
Total		100%	₹ 22,00,000

TERMS & CONDITIONS

- Quotation is an **estimate** for the built-up area and specification stated; final cost is billed on measured built-up area.
- Rates are valid for 30 days and are subject to revision for major cement/steel price changes.
- Any change in design, scope or specification will be charged as an extra with prior approval.
- Standard construction timeline: approximately **5–6 months** from advance & site handover.
- GST charged extra as applicable at the time of billing.

Assumptions used (please confirm / correct): Ground floor only · built-up ≈ 1,100 sq ft (derived from plan dimensions + walls) · Standard finish package · Tamil Nadu / South-India rates · pricing in INR at ₹2,000/sq ft. Tell me if any of these differ — e.g. G+1/G+2, Premium/Luxury finish, or a different city — and I will re-issue the figures.

For [Your Construction Firm Name]

Authorised Signatory

Accepted by Client

Mr. Murali — Signature & Date

This is a computer-generated quotation and is valid without signature for reference. · Prices indicative, exclusive of GST.